



USD 382 – Pratt, Kansas

REQUEST FOR PROPOSAL (RFP)

High School Track & Field Surface Resurfacing

Six-Lane Track & Field Facility

Approximate Area: 3,849 Square Yards

Proposal Due: March 9, 2026

FRONT-END RFP LANGUAGE

Proposals must be received no later than March 9, 2026 at the time specified by the Owner. Late proposals will not be considered.

Bidders are responsible for reviewing documents and visiting the site to verify quantities and conditions.

Proposal shall include base bid, alternate pricing for Gold Exchange Zones, specs, certifications, five references, schedule, and warranty.

Evaluation factors include cost, compliance, references, experience, system performance, and schedule.

USD 382 Pratt reserves the right to reject any or all bids and award in the district's best interest.

PART 1 – GENERAL (REVISED)

Contractor shall provide all labor and materials for removal, inspection, and installation of new synthetic surfacing.

Remove and dispose of existing synthetic oval and runway surfaces and inspect asphalt base.

Total approximate area is 3,849 square yards. Quantities are to be field verified.

Specific Scope of Work

- 1 Remove existing synthetic surfaces.
- 2 Inspect asphalt for slope, planarity, cracking, and contamination.
- 3 Report deficiencies before installation.
- 4 Install porous polyurethane system with SBR base and EPDM structural spray.
- 5 Stripe per World Athletics and NCAA rules.

PART 2 – CODES AND STANDARDS

System shall comply with World Athletics, NCAA, and ASTM performance standards for force reduction, deformation, friction, tensile strength, and elongation.

PART 3 – QUALITY ASSURANCE

- 1 Minimum seven years installer experience.
- 2 Minimum ten years manufacturer experience.
- 3 Provide five references and similar project list.
- 4 Submit product data and samples.
- 5 Provide governing body certification.

PART 4 – MATERIALS

- 1 Polyurethane primer.
- 2 SBR rubber base granules.
- 3 EPDM colored granules.
- 4 Polyurethane binder.
- 5 Structural spray coating.
- 6 Polyurethane line paint.

PART 5 – INSTALLATION

- 1 Asphalt must be properly compacted and cured.
- 2 Surface must meet tolerance and slope requirements.
- 3 Remove oil-contaminated areas.
- 4 Install base mat by mechanical paver.
- 5 Apply two-coat structural spray.
- 6 Install only under proper weather conditions.

PART 6 – STRIPING

All striping shall comply with current NFHS governing body rules and be certified accurate.

PART 7 – WARRANTY

Provide minimum five-year non-prorated warranty covering materials and workmanship.

ALTERNATE #1 – GOLD EXCHANGE ZONES

Provide separate line-item pricing for Gold Exchange Zones including materials and installation.

BID FORM

Base Bid: _____

Alternate #1: _____

Company: _____

Signature: _____

Date: _____

Five References Included: Yes / No